

COMPLETE PLANT FOR CONSTRUCTION OF LPG BOTTLES FOR DOMESTIC USE IN TWO OR TREE PIECES

LIGNE COMPLETE POUR LA CONSTRUCTION DE BOUTEILLES GPL EN DEUX OU TROIS PIECES POUR USAGE DOMESTIQUE

COPRIM - ITALY

MAIN ELEMENTS

- 1- Straightener line and cut from coils
- 2- Automatic shearing of disk
- 3- Drawing line
- 4- Beading machine
- 5- Degreasing tunnel
- 6- Welding line
- 7- Heat treatment of normalizing
- 8- Apparatus blowout test
- 9- Hydraulic test
- 10- Sandblasting and painting
- 11- Tap assembly machine
- 12- Water basin for tap test
- 13- Silk-screen machine
- 14- Air compressed station

ELEMENTS IMPORTANTS

- 1- Ligne de redressage et coupe de coils
- 2- Cisailles en automatique des disques
- 3- Lignes d'emboutissage
- 4- Detoureuse
- 5- Tunnel de degraissage
- 6- Ligne de soudure
- 7- Traitement thermique de normalisation
- 8- Banc eclatement
- 9- Test hydraulique
- 10- Ligne de sablage et peinture
- 11- Visseuse rubinets
- 12- Bac tenue rubinet
- 13- Station serigrafique
- 14- Station air comprimè

RESETTING USED BOTTLES

Complete plant only for resetting
Plant for resetting

RENOVATION BOUTEILLES

Ligne complet pour la renovation de
bouteilles utilisées





